



OREGON CITY

**LINE 1 (SEE BELOW)
PROJECT:**

LINE 2 (SEE BELOW)

LINE 3 (SEE BELOW)

LINE 4 (SEE BELOW)

9 1/4"

3 1/4" SPACE

2 3/4" LETTERING

2" SPACE

2 3/4" LETTERING

5 1/4" SPACE

2 1/2" LETTERING

5 3/4" SPACE

2" LETTERING

2" LETTERING

LINE 1	LINE 2	LINE 3	LINE 4
SEWER SYSTEM	PIPELINE EXTENSION PIPELINE REPLACEMENT PIPELINE REHABILITATION PUMP STATION	YOUR SEWER FEES AT WORK	PROJECT CONTACT INFORMATION
STORM SYSTEM	PIPELINE EXTENSION PIPELINE REPLACEMENT	YOUR STORMWATER RATES AT WORK	PROJECT CONTACT INFORMATION
STREET SYSTEM	IMPROVEMENT WIDENING RESURFACING RECONSTRUCTION	YOUR GAS TAXES AT WORK YOUR PAVEMENT MAINTENANCE UTILITY FEES (PMUF) AT WORK	PROJECT CONTACT INFORMATION
WATER SYSTEM	PIPELINE EXTENSION PIPELINE REPLACEMENT PUMP STATION RESERVOIR	YOUR WATER RATES AT WORK	PROJECT CONTACT INFORMATION
OTHER	OTHER	OTHER	OTHER

NOTES:

- SIGN TO BE 48" x 48", 0.100", ALUMINUM WITH 2.25" ROUNDED CORNERS. LEGEND TO BE BLACK ON WHITE. USE TYPE C FONT.
- MOUNT SIGN ON 4" x 6" WOOD POST DRILLED WITH 2-2" HOLES AT GROUND LEVEL AT 90° ANGLES FOR BREAKAWAY PROTECTION (MINIMUM 14' LONG), 7' TO BOTTOM OF SIGN.
- CONTRACTOR TO BE RESPONSIBLE FOR PURCHASING, MOUNTING AND MAINTAIN SIGN DURING CONSTRUCTION, REMOVE SIGN AND POST AFTER CONSTRUCTION. CONTRACTOR RESPONSIBLE FOR REPAIR OR REPLACEMENT OF DAMAGED SIGN DURING WORK.
- ENGINEER TO SPECIFY CONTENTS OF LINES 1, 2, 3 & 4.
- SIGN LOCATION TO BE APPROVED BY ENGINEER.
- SIGN INSTALLATION REQUIRED MINIMUM 2 BUSINESS DAYS PRIOR TO START.



Public Works Standard Drawings

PROJECT NOTIFICATION SIGN

SCALE NTS

DATE JAN '23 REV.

ENGR. DW DRAWN KAE

DRAWING NO. 531